Dated 9th July 1918.

It is hereby notified that a sum of Rs. 144-15-6, being the amount due to contractor Mr. N. Ramiah for diverting Storm Water Drain in Basavangudi Extension, is outstanding in the books of this office. If the same is not claimed by the party or claimant within three months from this date, the amount will be credited to Government.

Dated 20th July 1918.

Notice is hereby given that quotations will be received in the office of the Executive Engineer, Sanitary Division, up to 4 P.M., on 10th August 1918, for supplying the following drawing materials within fifteen days of the acceptance of the quotations, the successful competitor to deliver the drawing materials at this office premises. The outside competitors may deliver the same F. O. R., Bangalore City:—

Items	Per	Quantity.
Mathematical instrument 1st class in box complete. (P. Orr & Sons, Madras and Rangoon Paris make)	Set	2
Mathematical instrument 3rd class in box complete. (P. Orr & Sons, Madras and Rangoon Paris make)	"	4
Drawing board double elephant	No.	1
Saucers for mixing colours containing 6 in Nos.	"	2
Brass parallel ruler 12"	"	2
T.-squares wooden 36" vulcanite edge ...	"	2
Vulcanite set squares 6" of 45° (Winson and Newton) ...	"	2
Do 6" of 60° do ...	"	2
Wooden plotting scales six in Nos. in box with offsets (Winson and Newton)	"	3
Planimeter in box complete (Maker P. Orr & Sons) ...	"	1

N. SUBBA RAO,
Executive Engineer.

BANGALORE DIVISION.

Abstract Notification.

Attention is invited to the notification published in Part IV of the *Mysore Gazette*, dated the 11th July 1918, calling for tenders for the purchase of burnt stone slabs at Silledar Lines, Bangalore.

C. VIJAYARANGAM NAIDU,
Executive Engineer.

TUMKUR DIVISION.

Dated 13th July 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 5th August 1918, for constructing 7 blocks of 5 huts each for Barr Sepoys at Tumkur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1920.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. to 5 P.M., except Sundays and Government holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,500, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing 7 blocks of 5 huts each for Barr Sepoys at Tumkur," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract for constructing 7 blocks of huts each or 35 huts for Barr Sepoys at Tumkur.

No.	Items of work	Per	Single block	Additional block
			Quantity	Quantity
1	Earthwork excavation for foundation and filling in basement ...	C. yd.	22	16
2	Burnt stone in clay foundation and basement ...	C. ft.	1,001	731
3	Burnt brick in clay superstructure ...	"	1,175	783
4	Burnt brick in mortar do ...	"	242	205
5	Burnt stone slabs, 1 line dressed ...	S. ft.	136	136
6	Plastering with mortar, rough ...	Sqr.	8·54	5·48
7	Mud plastering ...	"	18·58	14·26
8	Colour washing ...	"	1·1	10
9	Whitewashing ...	"	11·89	9·53
10	Chunam pointing ...	"	2·54	1·71
11	Flooring with Cuddapah slabs on 3" concrete, etc., complete ...	"	2·79	2·75
12	Gravelling compound ...	C. yd.	4	3
13	Coping brick in chunam and plastering ...	R. ft.	67	48
14	Honneywood battened door, zinc painting ...	S. ft.	121	124
15	Honneywood battened windows ½" diameter, iron bars with painting, etc., complete.	"	26	26
16	Honneywood battened Almirah shutters with partition planks, etc. ...	"	18	18
17	Cement concrete drain V shaped 4"×4"×4" ...	R. ft.	24	22
18	Constructing seats in latrine with necessary trays ...	L. S.		
19	Honneywood work wrought and put up with oiling ...	C. ft.	18·32	80·05
20	Roofing with first class Mangalore tiles on teak reepers, etc. ...	Sqr.	6·39	5·30
21	Ridge tiles set in mortar and cement pointed ...	R. ft.	18	15
22	Building wall at gable ends with plastering, etc., complete ...	"	11½	11½
23	Plain cornice at gable ends with plastering, etc., complete ...	"	12	12
24	Ventilating or smoke tiles ...	No.	3	3
25	Taring woodwork ...	L. S.		
26	Clearing site, etc. ...	"		

Improving the drainage of Barr Lines at Tumkur.

No.	Details of work	Per	Quantity
1	Cement concrete drain 9"×9" including excavating for foundation and cement plastering, rear blocks.	R. ft.	1,395
2	Cement concrete drain 1'×1' including excavating foundation and cement plastering, leading water of all drains.	"	330
3	Opening out roads clearing sites levelling ground, etc. ...	L. S.	

N. G. KRISHNA IYENGAR,
Executive Engineer.

KADUR DIVISION.

Abstract Notification.

The attention of the public is invited to the notification published in *Mysore Gazette*, dated 18th July 1918, on pages 645—646, Part IV, calling for sealed tenders for constructing a District Forest Office at Chikmagalur.

K. PONNAPPA,
Executive Engineer.

MYSORE HEADQUARTER RANGE.

Dated 15th July 1918.

Notice is hereby given that sealed tenders will be received at the office of the Assistant Engineer, Headquarter Range, Mysore, up to the 12th August 1918, for constructing a New